

COMMITTEE AGENDA ITEM

VILLAGE OF HOFFMAN ESTATES

SUBJECT: 30-Day Progress Report from Commonwealth Edison
Regarding the Status of Resident Issues Concerning
Power Service

MEETING DATE: June 25, 2012

COMMITTEE: Public Works & Utilities

FROM: Daniel P. O'Malley, Deputy Village Manager
Joseph Nebel, Director of Public Works

PURPOSE: For Commonwealth Edison to provide a 30-day status reports on resident issues concerning power service as discussed at previous Public Works & Utilities Committee meetings.

BACKGROUND: You will recall on August 29, 2011, Commonwealth Edison appeared at the Special Public Works & Utilities Committee meeting to discuss the cause and remedies regarding numerous and lengthy power outages throughout the Village due to storms in June and July 2011. At that meeting, several residents raised other power issues and ComEd agreed to investigate those issues and report back to the Committee. ComEd appeared at both the October 24 and December 12, Public Works & Utilities Committee meetings with information on the proposed improvements. As the Committee requested ComEd attended the February 27, 2012 meeting and is to continue to provide 30-day progress reports.

DISCUSSION: Attached to this agenda item is the Commonwealth Edison 30-day progress update as provided to staff. As the last remaining item is scheduled to be completed on June 22nd this will be the last Commonwealth Edison update provided to the Committee regarding the power outages that occurred in the summer of 2011.

RECOMMENDATION: For discussion purposes.

**POST STORM/POCKET RELIABILITY FOLLOW UP
FOR THE VILLAGE OF HOFFMAN ESTATES**

COMMUNITY/AREA	FEEDER	OUTAGE HISTORY/CAUSE	RESOLUTION	PROJECTED START	PROJECTED COMPLETION
DRESDEN & HAMAN	E0210	2011-07-23 /TREE/VEGETATION RELATED	SWITCH TO FEEDER E147	COMPLETE	COMPLETE
WESTBURY & HAYMAN		2011-07-11/TREE/VEGETATION RELATED 2011-06-21/TREE/VEGETATION RELATED 2011-05-25/INTENTIONAL UNSCHEDULED 2010-10-27 /TREE/VEGETATION RELATED 2010-01-03/EQUIPMNT/MATERIAL FAILURE	INSTALL 3 TRIP SAVERS	COMPLETE	COMPLETE
		2009-10-06/TREE/VEGETATION RELATED 2009-10-06/WEATHER RELATED 2009-07-28/TREE/VEGETATION RELATED	TARGET TREE TRIMMING	COMPLETE	COMPLETE
HILLCREST	E148	2011-07-23/TREE/VEGETATION RELATED 2011-07-11/TREE/VEGETATION RELATED 2011-06-21/WEATHER RELATED 2009-03-29/TREE/VEGETATION RELATED	INSTALL 1400' OF HENDRIX CABLE	FEEDER WAS RECONDUCTORED (NEW LINES AND CROSS ARMS WERE INSTALLED; TARGET TREE TRIMMING WAS COMPLETED). HENDRIX CABLE NOT NEEDED.	COMPLETE
			REPLACE 1550' URD	COMPLETE	COMPLETE
			TARGET TREE TRIMMING	COMPLETE	COMPLETE
E THACKER	E5317X	2011-07-11/TREE/VEGETATION RELATED 2011-06-/WEATHER RELATED 2011-05-17 /WILDLIFE 2010-06-18 /WEATHER RELATED	INSTALLATION OF BYPASS FUSE ON FEEDER	COMPLETE	COMPLETE

		2010-05-08 /EQUIPMNT/MATERIAL FAILURE 2009-10-06 /WEATHER RELATED 2009-07-28 /WEATHER RELATED 2009-06-19/WEATHER RELATED	TARGET TREE TRIMMING	COMPLETE	COMPLETE
COMMUNITY/AREA	FEEDER	OUTAGE HISTORY/CAUSE	RESOLUTION	PROJECTED START	PROJECTED COMPLETION
BERKLEY & WASHINGTON	E141Y	2011-08-26 /INTENTIONAL UNSCHEDULED 2011-07-11 /TREE/VEGETATION RELATED 2011-03-01 /EQUIPMNT/MATERIAL FAILURE 2009-06-22 /EQUIPMNT/MATERIAL FAILURE (SAME EQUIPMENT MULTIPLE OUTAGES)	TARGET TREE TRIMMING INSTALL TRIP SAVERS (3)	COMPLETE COMPLETE	COMPLETE COMPLETE
CRESCENT LN	E141Y	2011-11-20 /UNKNOWN (wire down) 2011-11-18 /TREE/VEGETATION RELATED 2011-05-17 /EQUIPMNT/MATERIAL FAILURE 2009-02-16 /EQUIPMNT/MATERIAL FAILURE (DIFFERENT SECTIONS OF CABLE)	NO ACTION – OUTAGES WERE UNIQUE & NOT CHRONIC	N/A	N/A
MOHAVE/NEWTON	E141Y	2011-08-26 /INTENTIONAL UNSCHEDULED 2011-06-21 /TREE/VEGETATION RELATED 2011-03-01 /EQUIPMNT/MATERIAL FAILURE 2011-02-20 /WILDLIFE	NO ACTION – OUTAGES WERE UNIQUE & NOT CHRONIC	N/A	N/A
PARKVIEW CIRCLE (I USED 2013 W PARKVIEW CIR)	E1415	2011-08-21 /INTENTIONAL UNSCHEDULED 2011-08-20 /WEATHER RELATED 2010-10-02 /EQUIPMNT/MATERIAL FAILURE 2010-03-14 /EQUIPMNT/MATERIAL FAILURE	TARGETED TREE TRIMMING AROUND PARKVIEW CIRCLE. INSTALLATION OF TRIP SAVERS AT 2 LOCATIONS	COMPLETE COMPLETE	COMPLETE COMPLETE

COMMUNITY/AREA	FEEDER	OUTAGE HISTORY/CAUSE	RESOLUTION	PROJECTED START	PROJECTED COMPLETION
CASTAWAY LANE EXCESSIVE MOMENTARIES; THE MAJORITY WERE RELATED TO DISTRIBUTION AUTOMATION WORKING PROPERLY. THE METER DIDN'T CAPTURE ANY IRREGULARITIES (Nov. 2011)	E0225	2011-07-23 /WEATHER RELATED 2010-08-19 /INTENTIONAL SCHEDULED 2010-08-18 /EQUIPMNT/MATERIAL FAILURE 2010-08-09 /TREE/VEGETATION RELATED 2009-10-30 /TREE/VEGETATION RELATED 2009-08-28 /INTENTIONAL UNSCHEDULED 2009-07-28 /INTENTIONAL UNSCHEDULED 2009-06-20 /TREE/VEGETATION RELATED 2009-06-20 /EQUIPMNT/MATERIAL FAILURE 2009-06-19 /EQUIPMNT/MATERIAL FAILURE 2009-06-19 /EQUIPMNT/MATERIAL FAILURE	TARGET TREE TRIMMING & SWITCHING TO E3314 (THIS WILL FACILITATE LOAD BALANCING)	COMPLETE DESIGN WORK COMPLETE AS OF 5/16/12	COMPLETE 6/22/12